

Exam – Loading and Unloading Trucks with A-Frame Supports

True (T) or False (F)

1. **T** F When loading a flatbed truck with an A-frame, there should be a spotter on the ground and on the truck.
2. T **F** Slabs should never be loaded in rotation face-to-face and then back-to-back and so forth.
3. T **F** Slabs should always be loaded onto the A-frame in an increasing height series to prevent breaking. The tallest slabs should always be on the outside.
4. **T** F When unloading, spotters should be used to guide the slab at all times, one on the truck and one on the ground.
5. **T** F When using a boom to unload slabs from an A-frame, outriggers on the truck must be secured.
6. T **F** When unloading slabs, always bring the boom into position above the bundles after unstrapping them.
7. **T** F Once the bundle clears the bed of the truck it is lowered to 8-10 inches off the ground before moving to an A-frame on the ground.
8. **T** F A spotter should be used when moving slabs.
9. **T** F Rigging and lifting devices for stone slabs must be inspected before each use to ensure they are in good condition and good working order.